

Date:12.06.2017.

To,

Mr.

Dear Sir

Sub: Proposal for Solar Power Fencing Ground Mounting for 1000Mtrs perimeter.

Please find below the Detailed Commercial proposal for the 1000Meters Solar Power fencing as per the drawing provided by you.

BOQ WITH PRICING FOR MTRS. OF SOLAR FENCE SYSTEM

	<u>Fence Parameters:</u>	
1	Fence length in meters	1000
2	Fence height on Ground proposed in meter	6
3	Gap between strands in MM	150
4	Number of strands	8
5	Distance between posts in meters	3
6	Number of zones	1
7	Safety standards applicable	IEC 60335-2-76 with CE marking

Enclosures:

1. Price details with commercial terms and conditions.

We trust that our offer is in line with your requirement and in case you require any clarifications kindly Call / write to us.

Thanking you and assuring you of our best services all the times.

DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT (Rs.)
CS 250 Energizer include Alarm unit, On board LCD Keypad and controller duly CE marked	1	Each	36,750.00	36,750.00
Solar PV module of 12V / 75Wp with stand and charge controller	1	Each	9,000.00	9,000.00
Fencelite	1	Each	1,800.00	1,800.00
12V / 100 AH Battery	1	Each	9,750.00	9,750.00
Lightning Diverter Kit	1	Each	2,250.00	2,250.00
Neon Tester	1	Each	900	900.00
Outdoor console rack IP 65	1	Each	9,000.00	9,000.00
Intermediate posts KIWITAH of 2.4M length duly galvanized	329	Each	625	205,625.00
End / Corner post of 40 mm sq. post duly galvanized with support of length 2.4M	4	Each	2,980.00	11,920.00
Step posts of 25mm sq with 25x25x3mm T angular of adequate length		Each		Actual
Breakaway insulators	2,635	Each	10	26,350.00
End strain Hooks	64	Each	27	1,728.00
End strain insulators	64	Each	18	1,152.00
Joint Clamps	32	Each	9	288.00
Wire tightners	32	Each	54	1,728.00
HT wire 2.59mm	8,800.00	RMT	5.55	48,840.00
DI Cable with HDPE conduit	100	RMT	76	7,600.00
Warning sign board	100	Each	49	4,900.00
Super Earth kit	8	Each	1,800.00	14,400.00
Gate top Electrification to match fence on wall	2	Each	6,300.00	12,600.00
Fence Erection charges	8,800.00	RMT	2.5	22,000.00
Post erection	Customer scope			
Grand Total				428,581.00
TAXES @ 5% VAT	5%			20,329.00
TAXES @ 14% ST	14.00%			3,190.00
Transportation				17,200.00
NET total				469,300.00

Terms and Conditions

- 1. Final Invoice shall be raised based on actual supply.**
2. Road cutting at gates or elsewhere will be in Customer scope
3. Vegetation cleaning and site levelling is in Customer scope.
4. Price validity: 45 days
5. Warranty: 15 months from the date of delivery or 12 months from the date of commissioning whichever is earlier..
6. Payment: 80% along with order, 10% of material value against delivery and balance after commissioning.
7. Materials despatch: Within 30 days
- 8. Step posts (Sl. No. 9& 10) will be calculated based on site requirement and actual costing will be calculated accordingly.**

The Client has to make his payment through Cheque/ Demand Draft/ RTGS only no cash payments will be accepted.

Bank Details:

M/s. Greentek India Private Limited
Kotak Mahindra Bank
A/C NO—05522000005884
IFSC : KKBK0000552
Somajiguda BRANCH
Hyderabad

We hope the above is in line with your requirements. In case of any clarification, kindly feel free to contact us.

Thanking you and assuring you of our best attentions at all times to come.

For Greentek India Pvt Ltd.

Sachin Desai
9951067111

Sandhosh Kumar
9003132081